Testing and Characterization of Scintillator Tiles for the sPHENIX Hadronic Calorimeter.


Uttam Acharya


For the sPHENIX Collaboration DNP19 Meeting of APS Crystal City, Virginia, USA October 17, 2019



Quark Gluon Plasma (QGP)

- Extremely hot and dense state of matter.
- Produced at very high temperature(10¹²K) and density (1GeV/fm³) where nuclear matter get deconfined.
- Existed few microsecond after Big Bang.








Jets

Collimated beams of high momentum particles produced due to partonic

fragmentation in collision.



Proton
Hard Scattering
Proton


Jets in p+p Collision

- Jet particles loose energy into QGP and modifies the final energy.
- Study modification of jet energy comparing to p-p collision.



RHIC: Relativistic Heavy Ion Collider

- QGP machine located in Upton, New York.
- Capable of colliding many different atomic nuclei at different center of mass energies.






sPHENIX – A Jet Detector

• Upgrade to PHENIX.

• Full 2π acceptance in Azimuth.

• Pseudorapidity coverage $|\eta| < 1.1$


• Capable of full jet reconstruction.






10/14/19

RHIC





Essential components for measuring energy of jets.

-Outer HCal:- Located outside the magnet.




The Hadronic Calorimeter: Outer HCal

• Critical for precision jet measurements.

• 32 Sectors.

• 48 tower per sectors.

• 5 scintillator tiles per tower.



Sector


Each sector has 10 rows with 8mm gap between steel absorber.

24 tiles per row.

240 tiles in each sector.

HCal Tiles

- Made by Uniplast.
- Mixture of Polystyrene, Paraterphenyl, and POPOP, wrapped by Tedler.
- Wavelength shifting fiber routes the scintillation light to end of the tile where it is collected by SiPM's.
- 12 different shapes of tiles based on the particle trajectory.
- The signal of every five tiles is aggregated to form a tower.









Tile Inspection and Testing



- Tiles within a tower need to have similar behavior.
- Need to be tested before installation into HCal.
- Preliminary Test was done at Uniplast.




At GSU, we tested: Tile dimensions & Performance.

Uttam Acharya uacharya1@student.gsu.edu 10/14/19


Tile Inspection

Thickness Gauge

- Allow every tiles go through 8mm gap.
- Indicate those which do not go through it.







Dimension Tester


 Designed such that dimension of all tiles shape be easily measured.



Tile Testing



- Test stand built at BNL.
- CAEN DT5702 FEB mounted on top to quantify the signal.
- Test tiles by measuring response to the cosmic rays.
- 10 Channels:- test 8 tiles at a time.
- Top and bottom tiles are reference tiles.
- Reference tiles allow us track the performance of tile over the course of production.






Performance Characterization

- Cosmic rays strike tiles, produce scintillation light.
- Scintillation light is captured by SiPM and converted into an ADC count: forms the spectrum for all channels.
- ADC spectra is fitted by Landau Distribution with its most probable value(MPV) used to sort tile's performance.
- Take average of the MPV's of the reference tiles and divide each test tile's MPV by this average called "Performance Ratio".


Performance Ratio(PR)=
$$\frac{MPV_{tile}}{\langle MPV_{Refs} \rangle}$$



Performance Characterization

- Received 1560 tiles. (20% of total tiles).
- 12 tiles were used as reference tiles.
- Only 3 tiles were physically damaged.
- Global Performance Distribution

- Tested 1545 tiles.
- Used performance ratio(PR) to sort 250 tiles in the tower.
- Rejected tiles with PR < 0.8
 - 27 tiles (1.74%).
- Accepted Tiles PR >0.8
 - -1518 tiles (98.26%).




14



Summary and Outlook

- 1,560 of 7,680 tiles received, tested 1545 tiles. Few tiles failed the criteria of tile selection.
- Tested tiles shipped to BNL and installed in HCal Sectors.
- Remaining tiles' production and testing procedure has already started:- first shipment of 94 boxes arrived at GSU for test.
- Estimate to finish tile testing in about 12 months in this pace.
- On track to meet the target of first test starting in 2023.









THANKYOU





10/14/19

Back Up

REPRODUCIBILITY TEST

- ➤ Does tile have same response when the channel is changed?
- Want to reproduce the same response when they go in the tower.








TEMPERATURE TEST

- ➤ Lab temperature changes by 2 degrees over a day.
- ➤ Distribution shows no specific trend in response to temperature change. Data is flat.

Global Distribution





LIGHT LEAK TEST

- Performed Test by turning room lights on and off of the lab.
- Results were consistent.
- Lights makes no difference in performance of the tiles.

